

ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COSTS

Project #2 - 2009
 Cummins Single County Ditch Petition No. 691
 Jefferson Township

Williams County Engineer
Dennis M. Bell, P.E., P.S.

12953 County Road G
 Bryan, OH 43506
 419-636-2454
 Fax 419-636-8687

Date: 9-24-08 Revised:

Ref. No.	Item	Description	Unit	Quantity	Unit Price	Estimated Cost
DRAINAGE						
1	202	Clearing and Grubbing	LUMP	1.0	\$500.00	\$500.00
1	603	36" Type C Conduit, 707.33	FT	1,294.0	\$45.00	\$58,230.00
2	603	24" Type C Conduit, 707.33	FT	20.0	\$22.00	\$440.00
3	603	<6" Type F Conduit for Farm Tile	FT	100.0	\$4.00	\$400.00
4	603	>6" Type F Conduit for Farm Tile	FT	100.0	\$6.00	\$600.00
5	604	4-4-B Catch Basin	EA	2.0	\$2,000.00	\$4,000.00
EROSION CONTROL						
6	207	Inlet Protection Filter Fabric Fence	FT	40.0	\$4.00	\$160.00
7	659	Seeding and Mulching	SY	100.0	\$0.30	\$30.00
8	601	Dumped Rock Fill, Type C	CY	7.0	\$70.00	\$490.00
MISCELLANEOUS						
11		Contingencies	lump	1.0	\$5,385.00	\$5,385.00
TOTAL ESTIMATE						\$70,235.00

Respectfully Submitted,

 Dennis M. Bell, P.E., P.S.
 Williams County Engineer

 January 16, 2009
 Date

