

**OFFICIAL BID FORM - REVISED BY ADDENDUM 1**

**ITEM 00300**

**Williams County Commissioners**

Township Road N.30 & 16 Reconstruction  
Menard's Distribution Center Area  
Williams County, Ohio

**Williams County Engineer**

12953 County Road G  
Bryan, OH 43506  
419-636-2454 Fax 419-636-8687  
email: dbell@wmsco.org

Date: 7-20-09 Revised: 11-4-09

Ref	Item	Description	Unit	Quantity	Unit Price	Cost
<b>ROADWAY</b>						
1	201	CLEARING AND GRUBBING	LUMP	1.00		
2	202	PIPE REMOVED, 24" AND UNDER	FT	200.00		
3	202	CATCH BASIN REMOVED	EACH	9.00		
4	203	EXCAVATION (Roadway Ditches)	LUMP	1.00		
5	203	EMBANKMENT (Roadway Ditches)	LUMP	1.00		
6	203	SOFT SUBGRADE UNDERCUT EXCAVATION	CU YD	500.00		
7	304	SOFT SUBGRADE UNDERCUT EMBANKMENT	CU YD	500.00		
8	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22 (Patches)	CU YD	6.00		
9	604	MONUMENT BOX	EACH	5.00		
<b>EROSION CONTROL</b>						
10	601	TYPE C DUMP ROCK FILL	CU YD	20.00		
11	SS832	STORM WATER POLLUTION PREVENTION PLAN - SP3	LUMP	1.00		
12	SS832	EROSION CONTROL	LUMP	1.00	\$5,000.00	\$5,000.00
13	659	SEEDING AND MULCHING	SQ YD	43335.00		
14	659	COMMERCIAL FERTILIZER	TON	3.90		
<b>DRAINAGE</b>						
15	203	EXCAVATION (Drainage Ditch)	LUMP	1.00		
16	203	EMBANKMENT (Drainage Ditch)	LUMP	1.00		
17	603	6" and SMALLER CONDUIT, TYPE E (CONTINGENCY)	FT	200.00		
18	603	8"-12" CONDUIT, TYPE E (CONTINGENCY)	FT	200.00		
19	603	8" CONDUIT, TYPE B, 707.33	FT	13.00		
20	603	12" CONDUIT, TYPE B, 707.33	FT	353.00		
21	603	12" CONDUIT, TYPE C, 707.33	FT	104.00		
22	603	15" CONDUIT, TYPE B, 707.33	FT	35.00		
23	603	18" CONDUIT, TYPE B, 707.33	FT	53.00		
24	603	24" CONDUIT, TYPE B, 707.33	FT	161.00		
25	603	24" CONDUIT, TYPE C, 707.33	FT	1267.00		
26	603	36" CONDUIT, TYPE B, 707.33	FT	60.00		
27	603	24" JACKED PIPE	FT	120.00		
28	603	36" STEEL ENCASMENT	FT	120.00		

29	604	2-2B CATCH BASIN	EA	7.00		
30	604	2-3 CATCH BASIN	EA	3.00		
31	604	CAST IN PLACE HEADWALL	EA	1.00		

**PAVEMENT**

32	411	AGGREGATE BASE (Berm Stone)	CU YD	314.00		
33	407	TACK COAT	GAL	<b>3491.00</b>		
34	408	PRIME COAT	GAL	<b>5831.00</b>		
35	448	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 PG64-22	CU YD	720.00		
36	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	CU YD	970.00		
37	Special	SOIL STABILIZATION	SQ YD	12959.00		

**TRAFFIC CONTROL**

38	614	MAINTAIN TRAFFIC	LUMP	1.00		
39	630	TRAFFIC SIGNS AND SIGN SUPPORTS	LUMP	1.00		
40	642	PAVEMENT MARKINGS	LUMP	1.00		
41	Special	MAILBOX SUPPORTS	EA	8.00		

**MISCELLANEOUS**

42	623	CONSTRUCTION LAYOUT STAKES	LUMP	1.00		
43	624	MOBILIZATION	LUMP	1.00		
44	624	PREMIUM FOR CONTRACT PERFORMANCE BOND	LUMP	1.00		

**TOTAL BASE BID**

IT IS THE COMMISSIONER'S INTENT THAT ALL WORK REQUIRED IN THE BID OR SPECIFICATIONS BE INCLUDED IN THE TOTAL BASE BID. IF A ITEM IS REQUIRED TO COMPLETE THE WORK, BUT IS NOT SPECIFICALLY LISTED ABOVE, THE CONTRACTOR SHALL INCLUDE THE ITEM IN OTHER BID ITEMS.

SUBMITTED BY:		
_____	_____	
BIDDER	DATE	